PART NUMBER 77754-21

COMPLAINT

SECONDARY COMPLAINTS

Cause

Wear of the bore plug in the forward and reverse abuse valve bores can allow valuable oil pressure to exhaust.

CORRECTION

This increased diameter plug restores proper clearance in the valve body and requires no tools for installation.


Forward/ Reverse Abuse Bore Plug

77754-21

1 Bore Plug

Delayed reverse, burned 3-4 clutch

• 3-2 downshift tie-up • Burned 2-4 band • Burned low/reverse clutch



Sonnax Part Summary

The bore plug in 4L60-E units is held loosely in place with a coiled spring pin, allowing the opposing spring and oil pressure forces to stroke it within the bore. This constant oscillation causes the plug to wear and allows PR oil at the low overrun valve and 3-4 clutch oil at the 3-2 downshift valve to exhaust at the abuse valves. This excessive oil loss can result in delayed apply of the low/reverse clutch and a tie-up of the 3-4 clutch and 2-4 band. The Sonnax bore plug 77754-21 resolves these problems. The plug is used in two locations in the valve body: to separate the forward abuse and low overrun valves, and to separate the reverse abuse and 3-2 downshift valves.

Features & Benefits

- The Sonnax plug has an increased diameter to restore proper valve body clearance in the circuits.
- The plug has a smaller retaining pin hole to reduce plug movement that results in wear.
- No tooling is required for this bore plug.

